

SUPPLEMENTAL BID BULLETIN

**Republic of the Philippines
PHILIPPINE INTERNATIONAL CONVENTION CENTER
PICC Complex, 1307 Pasay City
BIDS AND AWARDS COMMITTEE (BAC)**

January 10, 2025

**SUPPLY OF LABOR, MATERIALS AND INSTALLATION OF STEEL MEZZANINE
STRUCTURE AT THE STORAGE PANTRY**

ADDENDUM NO. 01

This Addendum is issued to amend/revise certain provisions of the Bid Documents for the above-captioned procurement. Said amendments are as follows:

I. Section III- Bid Data Sheet has been revised to read as follows:

- ITB Clause 20
 - Post-Qualification Documents
 - Within a non-extendible period of five (5) calendar days from receipt of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit the following:
 1. 2023 Income and Business Tax returns with proof of payment;
 2. Sections III and V of the Bid Documents, signed on each and every page by the bidder's authorized representative;
 3. Company profile with organizational chart and sketch of office location;
 4. Resume of key personnel who will be assigned to the project;
 5. Certification that the participating bidder has conducted ocular inspection of the subject requirements;
 6. Submit a **layout** drawing containing all the material specifications and dimensions of the **structural design computation, signed and sealed by the structural engineer;**
 7. Actual samples (**at least 6 inches but not more than 1 foot** in length of the beams, handrail, skirtboard, ramp and deck flooring) of the materials to be used;

8. Certificate of Satisfactory Completion and Acceptance of previous PICC projects undertaken within the last five (5) years, if any.

II. Section V-Special Conditions of Contract have been changed to read as:

- GCC Clause 14
 - Payment
 - **Two weeks after acceptance** of the Facilities and Property Division's authorized representative and upon submission of the following:

III. Section VI- Technical Specifications have been changed to read as:

- **A. Other Conditions:**
 - **15.** Upon inspection and acceptance by end-user representative, CONTRACTOR may submit billing statement for finished works. **(DELETED)**

IV. Section VIII-Checklist of Technical and Financial Documents has been changed to read as:

- **II. FINANCIAL COMPONENT ENVELOPE**
 - **k. Corrected copy of** the Bill of Quantities (Section VIII)

The corrected copies are attached. Bidders are advised to replace their original copies with the corrected copies.

For guidance and information of all concerned.


ELIZABETH B. AGUILA
Vice-Chairperson

Received by:

(Signature over printed name)

Telephone/Fax No. _____

Date: _____

Name of Company: _____

| | |
|------|---|
| 17.1 | <p>The place of bid</p> <p style="text-align: center;">BAC CONFERENCE ROOM Function Room B. 2nd Floor, Secretariat Building PICC Complex, 1307 Pasay City</p> <p>The date and time of bid opening is January 20, 2025 at 11:00 a.m.</p> <p>In case the Bids cannot be opened as scheduled due to justifiable reasons, the BAC shall take custody of the Bids submitted and the opening of Bids shall be at 11:00 a.m. of the next working day.</p> |
| 19.2 | Not Applicable. |
| 20 | <p>Within a non-extendible period of five (5) calendar days from receipt of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit the following;</p> <ol style="list-style-type: none"> 1. 2023 Income and Business Tax returns with proof of payment; 2. Sections III and V of the Bid Documents, signed on each and every page by the bidder's authorized representative; 3. Company profile with organizational chart and sketch of office location; 4. Resume of key personnel who will be assigned to the project; 5. Certification that the participating bidder has conducted ocular inspection of the subject requirements; 6. Submit a <i>layout</i> drawing containing all the material specifications and dimensions of the <i>structural design computation, signed and sealed by the structural engineer.</i> 7. Actual samples (<i>at least 6 inches but not more</i> than 1 foot in length of the beams, handrail, skirtboard, ramp and deck flooring) of the materials to be used; and 8. Certificate of Satisfactory Completion and Acceptance of previous PICC projects undertaken within the last five (5) years, if any. |
| 21 | <p>The following documents shall be submitted, together with the Performance Bond, within ten (10) calendar days after the receipt of the Notice of Award. Such documents shall form part of the contract;</p> <ol style="list-style-type: none"> 1. Project Schedule/ Work Program and S-curve; 2. Project Safety and Health Program signed by the Safety Officer; and 3. PERT/CPM. |

expenses which may develop on account or failure of the Contractor to make an accurate examination of present or future factors that may affect the cost of the execution.

6. The Contractor shall carry out the works properly and in accordance with this contract.
7. The Contractor shall be responsible for the safety of all activities on the site.
8. The Contractor shall free the PICC and its personnel from and against all liability for damages arising from injuries or liabilities to persons or damages to property occasioned by any act of omissions of the Contractor including any and all expenses which may be incurred by PICC and its personnel in the defense of any claim, action or suit.
9. The Contractor shall ensure that any work that may affect the operation, security and image of the Center shall be coordinated properly with the FPD representative and shall be done in accordance with the Center's approved policies and regulations.
10. The Contractor shall bear all cost of rework and restoration of damaged properties due to Contractor's poor workmanship or negligence.
11. The Contractor must submit a list of personnel to be assigned to the project with a Police/NBI Clearance before the start of the installation of the Mezzanine Rack.
12. The Contractor agrees that the time of work shall be from Monday to Sunday, 8am to 5pm or in the most convenient time in favor of PICC.
13. Any works that may affect the operation and security measures of PICC shall be coordinated properly and shall be done in accordance with PICC approved schedule.
14. Deliveries may be made on a staggered basis at a time and day when there is no events in the corresponding area for delivery. It must be scheduled in the most convenient time in favor of PICC.

Corrected Copy

| ITEM NO. | DESCRIPTION | QTY. | UNIT | UNIT DIRECT COST | | ESTIMATED DIRECT COST | MARK-UPS | | TOTAL MARK-UP | | VAT 12 % | TOTAL INDIRECT COST | TOTAL COST | UNIT COST |
|--------------------------------------|--|------|------|------------------|------------|-----------------------|----------|----------|---------------|-------|----------|---------------------|------------|-----------|
| | | | | MATERIAL COST | LABOR COST | | OCM % | PROFIT % | % | VALUE | | | | |
| (1) | (2) | (3) | (4) | (5A) | (5B) | (6) | (7) | (8) | (10) | (11) | (12) | (13) | (14) | (15) |
| (3 x 5) (6 x 10) (11 x 12) (14) (15) | | | | | | | | | | | | | | |
| 1 | Mezzanine (New Installation) | | | | | | | | | | | | | |
| A. | STRUCTURE WORKS | | | | | | | | | | | | | |
| | Column : H212 150 x 150 x 5.0mm with base plate | 1 | lot | | | | | | | | | | | |
| | Column : H2661 150 x 150 x 5.0mm with base plate | | | | | | | | | | | | | |
| | Column : H2362 150 x 150 x 5.0mm with base plate | | | | | | | | | | | | | |
| | Main beam : L4125 298 x 149 x 5.5 x 8mm | | | | | | | | | | | | | |
| | Secondary beam : L3405 150 x 75 x 5x 7mm | | | | | | | | | | | | | |
| | Secondary beam : L2005 150 x 75 x 5x 7mm | | | | | | | | | | | | | |
| | Secondary beam : L1400 150 x 75 x 5x 7mm | | | | | | | | | | | | | |
| | Floor : 198 x 40 x2.5mm with reinforced rib without hole | | | | | | | | | | | | | |
| | Floor fasteners and parts | | | | | | | | | | | | | |
| | Horizontal & Back bracing : L6000 50 x50 x 4.0mm | | | | | | | | | | | | | |
| | Horizontal with 1 set sliding gate : H1100 | | | | | | | | | | | | | |
| | Steel straight ladder : H3500 x W1000mm | | | | | | | | | | | | | |
| | Accessories | | | | | | | | | | | | | |
| | Ramp with mid landing : L16500 x D2000 x H3500 | | | | | | | | | | | | | |
| | - Upright Frame : L2000 x D1050 x H975 -H9525mm-1.2 level beam | | | | | | | | | | | | | |
| | - Upright post : 90 x 70 x 2.0mm with connect plate, beam 100 x 50 x 1.5mm | | | | | | | | | | | | | |
| | - Plate beam : 100 x 50 x 1.5mm | | | | | | | | | | | | | |
| | - Ramp : 3.0mm pattern plate | | | | | | | | | | | | | |
| | - Hand rail : H1000mm | | | | | | | | | | | | | |
| B. | ELECTRICAL WORKS | | | | | | | | | | | | | |
| | Lighting System | 1 | lot | | | | | | | | | | | |
| | - LED bulbs 25 watts with receptacle | | | | | | | | | | | | | |
| | - Electric wire 2.5mm2 THHN | | | | | | | | | | | | | |
| | - Conduits 1/2" diamete + junction box | | | | | | | | | | | | | |
| | - Switch single with box | | | | | | | | | | | | | |
| | - Accessories - screws, cable ties, solvent cement, pvc tapes, etc. | | | | | | | | | | | | | |
| C. | GENERAL REQUIREMENTS | | | | | | | | | | | | | |
| | Installation | 1 | lot | | | | | | | | | | | |
| | Delivery | 1 | lot | | | | | | | | | | | |
| | Mobilization and demobilization | 1 | lot | | | | | | | | | | | |
| | Rental of forklift for lifting/lifting | 1 | lot | | | | | | | | | | | |
| | Manpower and supervision | 1 | lot | | | | | | | | | | | |
| | TOTAL A + B + C | | | | | | | | | | | | | |
| | TOTAL CONSTRUCTION COST | | | | | | | | | | | | | |

Prepared by:

Signature over printed name

Date

PROJECT : SUPPLY OF LABOR AND MATERIALS FOR THE INSTALLATION OF STEEL MEZZANINE STRUCTURE AT THE STORAGE PANTRY
LOCATION : PICC STORAGE PANTRY

| ITEM NO. | DESCRIPTION | QTY. | UNIT | UNIT DIRECT COST | | ESTIMATED DIRECT COST | MARK-UP#5 | | TOTAL MARK-UP | | VAT 12 % | TOTAL INDIRECT COST | TOTAL COST | UNIT COST |
|--------------------------------|--|------|------|------------------|------|-----------------------|-----------|----------|---------------|----------|--------------|---------------------|------------|-----------|
| | | | | (5A) | (5B) | | OCM % | PROFIT % | % | VALUE | | | | |
| (1) | (2) | (3) | (4) | (5A) | (5B) | (6) | 7) | (8) | (10) | (11) | (12) | (13) | (14) | (15) |
| | | | | | | (3 X 5) | | | (7 + 8) | (6 X 10) | 12% (6 + 11) | (11 + 12) | (6 + 13) | (14/3) |
| 2 | Mezzanine (Disinstalling of Existing Structure and Extension) | | | | | | | | | | | | | |
| A. STRUCTURE WORKS | | | | | | | | | | | | | | |
| | Column : H3212 150 x 150 x 5.0mm with base plate | 1 | lot | | | | | | | | | | | |
| | Main beam : L4700 298 x 149 x 5.5 x 8mm | | | | | | | | | | | | | |
| | Secondary beam : L3509 150 x 75 x 5 x 7mm | | | | | | | | | | | | | |
| | Secondary beam : L3369 150 x 75 x 5 x 7mm | | | | | | | | | | | | | |
| | Floor : 198 x 40 x 2.5mm with reinforced rib without hole | | | | | | | | | | | | | |
| | Floor fasteners and parts | | | | | | | | | | | | | |
| | Horizontal & Back bracing : L6000 50 x50 x 4.0mm | | | | | | | | | | | | | |
| | Handrail without gate : H1100 | | | | | | | | | | | | | |
| | Accessories | | | | | | | | | | | | | |
| B. ELECTRICAL WORKS | | | | | | | | | | | | | | |
| | Lighting System | 1 | lot | | | | | | | | | | | |
| | - LED bulbs 25 watts with receptacle | | | | | | | | | | | | | |
| | - Electric wire 2.5mm ² THHN | | | | | | | | | | | | | |
| | - Conduits 1/2" diameter + junction box | | | | | | | | | | | | | |
| | - Switch single with box | | | | | | | | | | | | | |
| | - Accessories - screws, cable ties, solvent cement, pvc tapes, etc. | | | | | | | | | | | | | |
| C. GENERAL REQUIREMENTS | | | | | | | | | | | | | | |
| | Installation | | | | | | | | | | | | | |
| | Delivery | lot | 1 | | | | | | | | | | | |
| | Mobilization and demobilization | lot | 1 | | | | | | | | | | | |
| | Rental of forklift for lifting/rigging | lot | 1 | | | | | | | | | | | |
| | Manpower and supervision | lot | 1 | | | | | | | | | | | |
| | TOTAL A + B + C | | | | | | | | | | | | | |
| | TOTAL CONSTRUCTION COST | | | | | | | | | | | | | |

Prepared by:

Signature over printed name

Date

Corrected Copy